

**Groundwater Monitoring Well
Installation Report**

for

**Industrial Service Corporation
1633 S. Marsh Avenue
Kansas City, Missouri**

March 8, 1996

Prepared By:

**Deffenbaugh Industries, Inc.
18181 West 53rd Street
Shawnee, Kansas 66217**

INDUSTRIAL
SERVICE
CORPORATION

P.O. Box 3249
Shawnee, KS 66203
(913) 631-3300
Telefax No. (913) 631-1339

March 8, 1996


Mr. Bruce Stuart, P.E.
Hazardous Waste Program
Department of Natural Resources
P.O. Box 176
Jefferson City, Missouri 65102

Dear Mr. Stuart:

Enclosed are two copies of the Groundwater Monitoring Well Installation Report. This report was prepared for wells installed during field activities in July and August of 1995 west of the Industrial Service Corporation on Marsh Avenue in Kansas City, Missouri.

If you have questions or require additional information, please contact me at (913) 962-8353.

Sincerely,


James M. Cossairt, RG
Senior Project Geologist

JMC/mc

Enclosure

cc: **Ronald D. Deffenbaugh**
Dan R. Swyers, P.E.
Brent J. Nickel, P.G.
Tim J. Roche

Groundwater Monitoring Well
Installation Report

for

Industrial Service Corporation
1633 S. Marsh Avenue
Kansas City, Missouri

March 8, 1996

Prepared By:

Deffenbaugh Industries, Inc.
18181 West 53rd Street
Shawnee, Kansas 66217

TABLE OF CONTENTS

1.0	INTRODUCTION	1
2.0	MONITORING WELL INSTALLATION	2
2.1	Preliminary Activity	2
2.2	Methodology	2
2.3	Well Development	4
2.4	Waste Disposition	4
3.0	DATA ANALYSIS	5
3.1	Geology	5
3.2	Hydrogeology	7
3.3	Analytical Results	8

FIGURES

FIGURE 1	Bedrock Contact Contour Map
FIGURE 2	Cross-section A - A'
FIGURE 4.3	Third Quarter Water Table Contour Map
FIGURE 4.4	Fourth Quarter Water Table Contour Map

APPENDICES

APPENDIX 1	Borelogs and Well Construction Diagrams
APPENDIX 2	Well Development Records
APPENDIX 3	Saturated Zone Data
APPENDIX 4	Soil Analytical Data
APPENDIX 5	Waste Authorization and Soil Analytical Data
APPENDIX 6	WasteWater Analytical Data

1.0 INTRODUCTION

Industrial Service Corporation (ISC) conducted field activities at the facility located at 1633 S. Marsh, Kansas City, Missouri during July and August, 1995. Total Environmental Services and Technologies (TEST), a division of Deffenbaugh Industries, was utilized to install, develop, and sample two monitoring wells as part of these field activities.

The work plan was prepared as part of a RCRA Facilities Investigation (RFI). The design and location of these wells serve two purposes. The first is to establish the extent of contaminant migration in the down gradient direction. Secondly, well GW8A was screened across the water table and GW8B was screened immediately above the bedrock contact to investigate the possible existence of dense non-aqueous phase liquids at that zone as well as aid in the understanding of the hydrogeology at the site.

A soil sample was collected at the water table and analyzed for the constituents of Appendix IX to aid in the determination of contaminant migration associated with groundwater. Soil samples were also collected at varying depths from the bedrock contact well for aquifer parameter testing. Laboratory grain size analysis and permeameters were used to provide estimates of hydraulic conductivity.

The wells were developed using a combination of pumping and bailing. They were then sampled during the first quarterly sampling event following well development. The samples were analyzed for the constituents of 40 CFR, Part 264, Appendix IX.

2.0 MONITORING WELL INSTALLATION

2.1 Preliminary Activity

Permission was granted from the Missouri Highway and Transportation Department to access and install monitoring wells in the right-of-way of northbound I-435, south of the Truman Road exit and west of the Livers Bronze Company. Utilities were cleared in this area prior to initiating field activities.

2.2 Methodology

Both borings were installed using a Mobile B-61 drill rig utilizing hollow stem augers and logged from a continuous core split-barrel sampler. Borelogs and well construction diagrams are included in Appendix 1.

Groundwater was encountered in the boring for GW8A at a depth of 7.8 feet. The boring was advanced to a total depth of 14.5 feet. The well was constructed of 2 inch PVC schedule 40 riser pipe with a threaded connection to ten feet of .010 slotted PVC screen. The filter pack was constructed of 10 - 20 Colorado Silica sand to a depth two feet above the screened interval. One foot of bentonite seal was installed above the filter pack and the well was completed with a steel flush mount cover installed in a concrete pad.

Field screening of soil samples was completed by heated head space analysis using a model 580B OVM. The instrument was calibrated using a 100 ppm Isobutylene standard prior to analysis. Samples were collected from depths of 5, 7, 11.5, and 13.5 feet. All samples yielded readings of 2 ppm. Background readings during the

testing were also 2 ppm. A sample was prepared for laboratory analysis from a depth of 11.5 feet.

The boring for GW8B was installed approximately 15 feet south of GW8A. Continuous sampling was employed to a depth of 34.8 feet when a change in the lithology of the saturated zone caused the sampling mechanism to become stuck. Once the mechanism was successfully released, drilling was resumed to a depth of 44.6 feet. Sampling was again attempted with the same result. Drilling was resumed, but further sampling efforts were discontinued. Bedrock was encountered at 72.0 feet, but was advanced to 73.0 feet in order to confirm that the bedrock contact had been identified.

The well was constructed of threaded 2 inch PVC schedule 40 riser pipe with a threaded connection to five feet of .010 slotted PVC screen. The filter pack was constructed of 10 - 20 Colorado Silica sand tremied to a depth three feet above the screened interval. Two feet of bentonite pellets were tremmied in place above the filter pack to form the seal. Approximately 51.5 gallons of potable water was used to facilitate the placement of the sand and bentonite pellets. Bentonite grout was tremmied in place above the seal while the balance of the augers were removed from the boring. The well was completed with a steel flush mount cover installed in a concrete pad.

A discrete soil sample was collected from a depth of 22 - 24 feet for laboratory hydrologic analysis. Due to the inability to use discrete sampling equipment below the 34.8 foot depth, samples collected below this elevation were collected from the

flights of the augers and sample depths are therefore approximate. Vibration of the drill rig at a depth of approximately 67 feet and below, indicate the gravel found in cuttings probably originated from this zone directly above the bedrock contact. Cuttings from the end of the lead auger confirmed that bedrock is a dark gray shale.

2.3 Well Development

Well development was completed on August 23, 1995. Water level measurements and development summaries were recorded on field sheets and are included in Appendix 2. Monitoring well GW8A was developed by bailing a quantity in excess of five times the calculated well volume. Monitoring well GW8B was developed by pumping a quantity of water in excess of five times the well volume plus the quantity of potable water introduced during well construction. Samples were collected from the development fluids for laboratory analysis pending final disposition.

2.4 Waste Disposition

Soil cuttings from borings as well as decontamination fluids and development water were collected and containerized in metal drums. These drums were stored on-site until analytical results could confirm the waste was non-hazardous. The wastewater was mixed with process waste water and treated through the ISC facility treatment system. Soils were disposed at the Johnson County Landfill under Johnson County Industrial Solid Waste Disposal Authorization Number 95-234. A copy of this authorization and analytical results are included in Appendix 5. Copies of wastewater analytical results are included in Appendix 6.

3.0 DATA ANALYSIS

3.1 Geology

Borelogs and well construction diagrams were prepared and are included in Appendix 1. The borelog for GW8B provides additional lithologic data from the surface to contact with bedrock in the predominant down gradient direction.

This new data point was included with twelve previously identified bedrock contact points to construct a top of bedrock contour map. This map is included as Figure 1. The contours generated depict a rather uniform slope in a generally west trending direction. Gradient varies from .40 in the area of the ISC facility to .20 in the area of the Livers Bronze Company employee parking area.

Figure 2 is a cross-section drawn from west to east providing the most appropriate interpretation of lithology below the site based on current data. This section is based on section B-B originally presented on Plate 4-1 from the Groundwater Monitoring Well Installation Report dated August 7, 1992. Modifications to this section were necessary to address variations in lithologic description as well as the approximate shape of the bedrock surface.

Although the lithologic description from GW8B depicts finer grained materials than that of boring TH1, the generally coarsening downward sequence remained consistent between them. Differences were determined to be due to variations in field interpretation of grain size rather than actual variations in the lithology. The sequence grades from clay, to silty clay, to clayey silt, to sand with gravel

immediately above the bedrock contact. Laboratory results of grain size analysis from GW8B confirm that lithology is more accurately described in terms of finer grained sediments.

Based on information provided by construction of the bedrock contour map, the profile of the bedrock contact was modified. The previous interpretation presented on Plate 4-1 depicted a steep east to west slope leveling to a narrow shelf at a depth of 35 to 40 feet immediately under the ISC facility. Continuing westward from about Marsh Avenue to boring TH1, the slope increased to a depth of approximately 70 feet where it begins to level to a depth of 77 feet. The profile presented in Figure 2 depicts a relatively uniform slope that more accurately honors the data control points.

Both sections are problematic in this regard however. The original profile was influenced by MW6 which is reported to have been installed at a total depth of 30 feet and did not contact bedrock. Boring GW2 clearly encountered bedrock at a depth of 20 feet, approximately 25 feet west MW6. The original profile was drawn below the 30 foot depth in the area beneath MW6, but ignored the bedrock contact at GW2.

The profile depicted in Figure 2 honors the bedrock contact located at GW2 in preference over the data from MW6. There are no field notes, boring logs, or well construction diagrams to support the data reported from MW6. The well was removed and plugged during field activities in January 1992. The log for this boring was summarized and presented in Appendix A of the Preliminary Site Evaluation for

a Remedial Investigation dated February 19, 1990. No other record exists. The log shows a correction was made when the entry reporting shale at a depth of 15 feet was stricken, marked wrong, and replaced with gray, firm, clay to a depth of 30 feet. If shale had actually been encountered at the depth of 15 feet, the log would further support the new profile. This summary page from the appendix as well as the boring log for GW2 are included with boring logs for the new wells in Appendix 1 for reference.

3.2 Hydrogeology

Results of grain size analysis and permeameter tests reveal much lower hydraulic conductivities for lithologies at the site than previously estimated. Data was obtained from three samples collected at varying depths from boring GW8B. The geometric mean was calculated from values reported, and the average hydraulic conductivity was determined to be 1.95×10^{-8} . The data is included in Appendix 3.


Figures 4.3 and 4.4 are water table contour maps prepared from data obtained during 3rd and 4th quarter monitoring and sampling events. These events occurred after construction and development of GW8A and GW8B. This data was previously submitted in the 1995 Annual Groundwater Monitoring Report. The maps indicate both flow direction and gradient mirror the bedrock contours from Figure 2. Flow direction is predominantly to the west and gradient is much steeper in the area of the ISC facility than the parking area to the west. Because wells at GW6B and GW8B are screened above the bedrock contact rather than at the water table, static water elevations from these points were not used to construct contours.

3.3 Analytical Results

A soil sample was collected from GW8A near the water table surface and submitted for laboratory analysis for the constituents listed in Appendix IX. Results indicated there were no detectable levels for any volatile organic compounds, semi-volatile organic compounds, pesticides, chlorinated herbicides, or PCB's analyzed. Metals detected in the sample were in the same range and did not exceed values obtained for background levels during March 1994 field activities. The laboratory data is included in Appendix 4 of this report.

Groundwater samples were collected from GW8A and GW8B during 3rd and 4th quarter sampling events and submitted for laboratory analysis for the constituents listed in Appendix IX. Results indicated no detectible levels for any of the contaminants analyzed. The laboratory data was previously submitted with quarterly reports as well as tabulated and summarized in the 1995 Annual Groundwater Monitoring Report.

FIGURES



LEGEND

- EXISTING SOIL BORING
- EXISTING WELLS
- ⊙ PLUGGED WELLS

BEDROCK CONTACT ELEVATIONS

EPA-R-2	748.00
EPA-R-3	740.57
TH1	691.00
SBH-1	786.40
SBH-2	780.40
B-1	783.20
B-3	787.00
GW1	790.20
GW2	765.26
GW3	744.37
GW4	744.00
GW6B	693.72
GW8B	692.47

SCALE: 1 INCH = 100 FEET

FIGURE


1

DATE	2-27-96
DESIGNED	JMC
DETAILED	JMC
CHECKED	BN



INDUSTRIAL SERVICE CORP.
1633 MARSH AVE.
KANSAS CITY, MO 64126

BEDROCK CONTACT
CONTOUR MAP



ALLUVIAL VALLEY / TERRACE LITHOLOGIES

- FILL: Gravel, Clay
- CLAY: Red, Gray w/Weathered Limestone Rubble
- CLAY: Silty, Brown to Dark Brown
- SILT & CLAY: Gray, Olive-Gray to Brown
- SILT & SAND: Fine Grained, w/Sparse Gravel
- SAND: Gravel, Boulders

BEDROCK LITHOLOGIES

- LIMESTONE: Medium Gray, Micritic, Jointed
- SHALE: Medium Gray to Black, Platy
- SHALE: Medium Gray to Light Greenish Gray, Slightly Silty, Grading Downward to Brownish Red, Silty

SCALE: 1 INCH = 50' VERTICAL EXAGGERATION: 2X

FIGURE 2
CROSS-SECTION A-A'

DATE	2-28-96
DESIGNED	JMC
DETAILED	JMC
CHECKED	BN

INDUSTRIAL SERVICE CORP.
1633 MARSH AVE.
KANSAS CITY, MO 64126

NOTES

- ⊕ EPA-R-1 MONITORING WELL INSTALLED BY USEPA (1988)
- ⊕ GW-5 TO 7 MONITORING WELLS INSTALLED BY ISC (1984)
- ⊕ GW-1 TO 4 MONITORING WELLS INSTALLED BY ISC (1982)
- ⊕ MONITORING WELLS SAMPLED

763.81
STATIC WATER LEVEL
(10 FEET ABOVE MEAN SEA LEVEL)

MONITORING WELLS GW-8B & GW-8C ARE SCREENED AT A DIFFERENT INTERVAL
AND WERE NOT USED IN CONSTRUCTING THE GROUND WATER CONTOURS
MONITORING WELL GW-8 WAS DRY AND NOT USED TO CONSTRUCT GROUND WATER CONTOURS




Figure 4.3

SCALE 1 INCH = 80 FEET	DATE 8-12-85
DESIGNED JGS	
DETAILED JGS	
CHECKED JW	


INDUSTRIAL SERVICE CORP
1833 MARSH AVE
KANSAS CITY, MO 64128

WATER TABLE
CONTOUR MAP

STATIC WATER LEVELS
MEASURED 8-8-85



LIVERS BRONZE CO
1833 MARSH AVENUE
KCMO



APPENDICES

APPENDIX 1

Borelogs and Well Construction Diagrams

TEST

TOTAL ENVIRONMENTAL SERVICES & TECHNOLOGIES

BOREHOLE LOG

LOCATION DESCRIPTION:

40' WEST OF LIVERS BLDG. AND 30' SOUTH OF BOX CULVERT
UNDER UNDER I-435 N. EXIT RAMP TO TRUMAN RD. RIGHT-OF-WAY

BORING/WELL ID: GW8A CLIENT: I. S. C.
WELL TAG ID: N/A ADDRESS: 1533 S. MARSH
RIG TYPE & NUMBER: MOBILE B-61/716 KANSAS CITY, MO
DRILLING METHOD: HOLLOW STEM PROJECT CODE: ISC-KC
SAMPLING METHOD: CONTINUOUS TEST ID: N/A
BORING DIAMETER: 7 5/8 TOTAL DEPTH: 14.5'
DATE DRILLED: 7/26/95
DRILLING CREW: G. GUERRA/ R. GEORGE/ H. GLEN
GEOLOGIST: M. COSSAIRT

ELEVATIONS (Ft)		
PAD	TOC	SWL
764.13	763.45	755.31

STATIC WATER LEVEL (BLS)		
While Drilling After Boring		
Depth (ft)	7.8'	8.14'
Time	?	?
Date:	7/26/95	8/23/95

SOIL SAMPLES	FIELD (ppm) ANALYSIS	LAB SAMPLES	DEPTH	LITHOLOGIC DESCRIPTION	LITHOLOGY	WELL INSTALLATION
			0	SOIL: DARK BROWN, FRIABLE		FLUSH-MOUNT COVER CONCRETE
				CLAY: DARK BROWN		BENTONITE-SEAL
GW8B-5'	2			CLAY: DARK BROWN, ROOT CAVATIES WET @ 7.8'		2" PVC RISER
GW8A-7'	2			NO SAMPLE: SAMPLE LOST FROM SAMPLER		2" SCREEN .01" SLOT
GW8A-11.5	2		-10	CLAY: GRAY, SILTY, IRON STAINING PRESENT BORING STOPPED @ 14.5'		FILTER-PACK
GW8A-13.5	2					NATURAL-MATERIAL

TEST

TOTAL ENVIRONMENTAL SERVICES & TECHNOLOGIES

BOREHOLE LOG

LOCATION DESCRIPTION:

40' WEST OF LIVERS BRONZE BLDG. AND 30' SOUTH OF BOX CULVERT
UNDER I-435 N. EXIT RAMP TO TRUMAN RD. RIGHT-OF-WAY


BORING/WELL ID: GW8B CLIENT: I. S. C.
WELL TAG ID: N/A ADDRESS: 1633 S. MARSH
RIG TYPE & NUMBER: MOBILE B-61/716 KANSAS CITY, MO
DRILLING METHOD: HOLLOW STEM PROJECT CODE: ISC-KC
SAMPLING METHOD: CONTINUOUS TEST ID: N/A
BORING DIAMETER: 7 5/8 TOTAL DEPTH: 73.0'
DATE DRILLED: 7/26/95 - 7/28/95
DRILLING CREW: G. GUERRA / R. GEORGE / H. GLENN
GEOLOGIST: M. COSSAIRT

ELEVATIONS (Ft)

PAD	TOC	SWL
764.47	763.97	753.52

STATIC WATER LEVEL (BLS)

While Drilling After Boring		
Depth (Ft)	7.8'	10.45'
Time	?	?
Date:	7/26/95	8/23/95



GROUND WATER OBSERVATION WELL REPORT

Project Name Industrial Service Corporation - Kansas City

Location 1633 S. Marsh, Kansas City, MO 64126

Installed by C. West, B.C. Millett

Inspected by _____

Method of Installation Mobile B-80, hollow stem augers, 7 7/8" borehole


Remarks Water entered at 9.5, 14.5, 16, 18-20

Plot./Well No. GW 2

Project No. _____

Date March 27, 1992

Time 1300



MONITORING WELL SOIL BORING INFORMATION FOR MONITORING WELLS

MW-1, MW-2, MW-3, MW-4, MW-5 AND MW-6

MW-1

Installed 10-11-86

0-2' unconsolidated fill,
 limestone, gravel
2'-15' brown, silty clay
15'-20' lt. brown silty clay
20'-30' clayey silt, lt. brown

MW-4

Installed 10-11-86

0-1' gravel
1-5' topsoil
5-15' reddish clay
15'-30' firm gray clay

MW-2

Installed 10-12-86

0-2' inconsolidated fill
 limestone, gravel
2'-15' brown, silty clay
16-21' moist lt.brown clayey silt

MW-5

Installed 10-11-86

0-1' gravel
1-5' topsoil
5-10' red, brown clay
10-30' brown clay, wet

MW-3

Installed 10-11-86

0-2' unconsolidated fill
 limestone, gravel
2-15' brown silty clay
15-30' lt. brown silty clay

MW-6

Installed 10-12-86

0-3' topsoil
3-15' red clay
~~15'~~ shale
15-30' gray clay, firm

APPENDIX 2

Well Development Records

151

Total Environmental Services & Technologies
18181 West 53rd Street • Shawnee, Kansas 66217

GROUND-WATER SAMPLING FORM

Well No. MW 8AWell Type: ☒ Monitor ☐ Extraction ☐ OtherWell Material: ☒ PVC ☐ St. Steel ☐ OtherDate 8-28-95 TimeSampled by JMC
(Initials)Job Name PSC-KC

Number

Recorded by Michelle Corrao
(Signature)

WELL PURGING

PURGE VOLUME

Casing Diameter (D in Inches):

☒ 2-inch ☐ 4-inch ☐ 6-inch ☐ OtherTotal Depth of Casing (TD in feet BTOC): 14.14Water Level Depth (WL in feet BTOC): 8.14

Number of Well Volumes to be purged (# Vols)

☐ 3 ☐ 4 ☒ 5 ☐ 10 ☐ Other

PURGE VOLUME CALCULATION

$$\left(\frac{14.14 - 8.14}{2} \right) \times \left(\frac{6.0}{2} \right)^2 \times 5 \times 0.0408 = 4.89 \text{ gallons}$$

TD (feet) WL (feet) D (inches) # Vols Calculated Purge Volume

PURGE TIME

10:15 Start 10:45 Stop 30 min Elapsed

PURGE RATE

Initial _____ gpm Final _____ gpm

ACTUAL PURGE VOLUME

8.0 gallons

FIELD PARAMETER MEASUREMENT

Minutes Since Pumping Began	pH	Cond. (umhos/cm)	T <input type="checkbox"/> °C <input type="checkbox"/> °F	Other

Minutes Since Pumping Began	pH	Cond. (umhos/cm)	T <input type="checkbox"/> °C <input type="checkbox"/> °F	Other

Meter Nos.

Observations During Purging (Well Condition, Turbidity, Color, Odor):

Discharge Water Disposal: ☐ Sanitary Sewer ☐ Storm Sewer ☐ Other

WELL SAMPLING

SAMPLING METHOD

☐ Baller - Type:☐ Submersible ☐ Centrifugal ☐ Bladder, Pump No.:☐ Same As Above☐ Grab - Type:☐ Other - Type:

SAMPLE DISTRIBUTION

Sample Series:

Sample No.	Volume/Cont.	Analysis Requested	Preservatives	Lab	Comments

QUALITY CONTROL SAMPLE

Duplicate Samples

Original Sample No.	Duplicate Sample No.

Blank Samples

Type	Sample No.

Other Samples

Type	Sample No.

IESI

Total Environmental Services & Technologies
18181 West 53rd Street • Shawnee, Kansas 66217

GROUND-WATER SAMPLING FORM

Well No. MW 2B
 Well Type: ☒ Monitor ☐ Extraction ☐ Other
 Well Material: ☒ PVC ☐ St. Steel ☐ Other
 Date 8-23-95 Time 1
 Recorded by Mike Cornett (Signature)
 Sampled by JML (Initials)

WELL PURGING

PURGE VOLUME

Casing Diameter (D in inches):

☒ 2-inch ☐ 4-inch ☐ 6-inch ☐ OtherTotal Depth of Casing (TD in feet BTOC): 70.69'Water Level Depth (WL in feet BTOC): 10.45'

Number of Well Volumes to be purged (# Vols)

☐ 3 ☒ 4 ☐ 5 ☐ 10 ☐ Other

PURGE VOLUME CALCULATION

$$\left(\frac{70.69' - 10.45'}{2.31} \right) \times \frac{2.31}{12} \times 5 \times 0.0408 = 49.75 + 51.5 \text{ gallons}$$

TD (feet) WL (feet) D (inches) # Vols

PURGE TIME

Start 10:00 PM Stop 2:45 PM Elapsed 4.75 hr

PURGE RATE

Initial gpm Final gpm

PURGE METHOD

☐ Baller - Type: ☐ Submersible ☐ Centrifugal ☒ Bladder, Pump No.: ☐ Other - Type:

PUMP INTAKE SETTING

☒ Near Bottom ☐ Near Top ☐ OtherDepth in feet (BTOC): 69' Screen Interval in feet (BTOC):from 67.5 to 72.5Calculated Purge Volume 100.65 gallons

ACTUAL PURGE VOLUME

105 gallons

FIELD PARAMETER MEASUREMENT

Minutes Since Pumping Began	pH	Cond. (umhos/cm)	T <input type="checkbox"/> °C <input type="checkbox"/> °F	Other

Minutes Since Pumping Began	pH	Cond. (umhos/cm)	T <input type="checkbox"/> °C <input type="checkbox"/> °F	Other

Observations During Purging (Well Condition, Turbidity, Color, Odor): Discharge Water Disposal: ☐ Sanitary Sewer ☐ Storm Sewer ☐ Other

WELL SAMPLING

SAMPLING METHOD

☐ Baller - Type: ☐ Submersible ☐ Centrifugal ☐ Bladder, Pump No.: ☐ Same As Above☐ Grab - Type: ☐ Other - Type:

SAMPLE DISTRIBUTION

Sample Series:

Sample No.	Volume/Cont.	Analysis Requested	Preservatives	Lab	Comments

QUALITY CONTROL SAMPLE

Duplicate Samples

Original Sample No.	Duplicate Sample No.

Blank Samples

Type	Sample No.

Other Samples

Type	Sample No.

APPENDIX 3

Saturated Zone Data

GeoSystems Engineering, Inc.

Geotechnical and Environmental Consultants

Date:

12-7-95

To:

Mr. Dan Taylor

Deffenbaugh Industries

P.O. Box 3220

Shawnee, Kansas 66203

Re:

Industrial Services Corporation - Jackson County, Missouri

Jcd No.

951113

Description:

Results of three grain size analysis and permeability tests for Boring MW-8B.

Remarks:

Yours truly,

GeoSystems Engineering, Inc.

By:


Richard L. Hanny, Jr.

cc:

SUMMARY OF LABORATORY TESTS

Depth (ft)	Moisture Content* (%)	Dry Density* (psf)	Clay Content (%)	Liquid Limit (%)	Plastic Limit (%)	Plasticity Index (%)	Coeff. of Perm (cm/sec)
22-24	23.1	95	35	39	23	16	9.6×10^{-3}
48-50	21.6	108	42	45	20	25	5.9×10^{-9}
68-70	22.9	97	35	48	21	27	1.3×10^{-8}

* = Before Permeability Test



GRAVEL		SAND			SILT or CLAY
Coarse	Fine	Coarse	Medium	Fine	

GRAIN SIZE DISTRIBUTION CURVE

Boring No.	Sample No.	Depth, ft.	Description	Unified Symbol	Natural WC, %	LL, %	PL, %	PI, %
MW-8B		22.0	Clayey silt, gray brown mottled	CL-ML		39	23	16

Industrial Services Corporation


Jackson County, Missouri

Approved By SMM

Project No. 951113

ASTM D-421, D-422, C-136, C-117

***GeoSystems
Engineering, Inc.***



GRAVEL		SAND			SILT or CLAY
Coarse	Fine	Coarse	Medium	Fine	

GRAIN SIZE DISTRIBUTION CURVE

Boring No.	Sample No.	Depth, ft.	Description	Unified Symbol	Natural WC, %	LL, %	PL, %	PI, %
MW-8B		48.0	Lean clay w/ silt, dk brown, trace gravel	CL		45	20	25

Industrial Services Corporation


Jackson County, Missouri

Approved By SMM

Project No. 951113

ASTM D-421, D-422, C-136, C-117

**GeoSystems
Engineering, Inc.**



GRAVEL		SAND			SILT or CLAY
Coarse	Fine	Coarse	Medium	Fine	

GRAIN SIZE DISTRIBUTION CURVE

Boring No.	Sample No.	Depth, ft.	Description	Unified Symbol	Natural WC, %	LL, %	PL, %	PI, %
MW-8B		68.0	Lean to fat clay, dk gray brn, w/ gravel	CL-CI		48	21	27

Industrial Services Corporation

Jackson County, Missouri

Approved By SMM

Project No. 951113

ASTM D-421, D-422, C-136, C-117

**GeoSystems
Engineering, Inc.**

PERMEABILITY TEST RESULTS (ASTM 5084)

Project Name Industrial Services Job No. 951113
Date 11-30-95

Boring No. MW-88 Boring No. MW-88
Sample Type Sample Type
Sample Depth 22-24' Sample Depth 48-50'
Sample Description Sample Description

Before			Units	Before			Units
Moisture Content, w	23.1	26.9	%	Moisture Content, w	21.6	23.2	%
Dry Unit Weight, Dd	95.2	95.5	pcf	Dry Unit Weight, Dd	107.6	105.9	pcf
Height, L	3.85	3.85	inches	Height, L	3.65	3.65	inches
Diameter, d	2.80	2.80	inches	Diameter, d	2.75	2.75	inches
Degree of Saturation, Sr	81.0	95.0	%	Degree of Saturation, Sr	103.1	106.0	%
Applied Pressure (influent):		44.4	psi	Applied Pressure (influent):		45	psi
Applied Pressure (effluent):		43	psi	Applied Pressure (effluent):		43	psi
Hydraulic Gradient:		10		Hydraulic Gradient:		11	

Test Number	Time (sec)	Influent Reading	Effluent Reading	Test Number	Time (sec)	Influent Reading	Effluent Reading
1	Start	0	13.7	1	Start	0	7.3
	Finish	75660	16.1		Finish	93480	7.5
2	Start	0	16.1	2	Start	0	9.0
	Finish	76620	18.6		Finish	73080	9.2
3	Start	0	18.6	3	Start	0	9.2
	Finish	92640	21.6		Finish	76140	9.3
4	Start	0	21.6	4	Start	0	9.3
	Finish	32040	22.7		Finish	76740	9.5

Hydraulic Conductivity "K" (cm/sec)	1	8.3E-08	Hydraulic Conductivity "K" (cm/sec)	1	6.6E-09
	2	9.3E-08		2	5.3E-09
	3	9.9E-08		3	5.1E-09
	4	1.1E-07		4	6.7E-09
Avg. k		9.6E-08	Avg. k		5.9E-09

Assumed Specific Gravity, SG 2.70 Area of Tube, a 0.9721
Permeant: Deaired Tap Water

Formulas:

Permeability (Falling Head-Rising Tailwater Test)

$$k = (a^2 L / 2 A t) \ln(h_0 / h_1)$$

Degree of Saturation

$$Sr = w \cdot SG / e$$

$$Dd = (SG / (1 + e)) Dw$$

$$Sr = (w \cdot SG) / ((SG \cdot Dw / Dd) - 1)$$

F:\qpro\permnew.wq2 6/20/95

k Hydraulic Conductivity (cm/sec)
a Area of Tube (cm²)
L Height or Length of Sample (cm)
A Area of Sample (cm)
t Time of Test Interval (sec)
h₀ Height of Head at Start of Test Interval (cm)
h₁ Height of Head at End of Test Interval (cm)
Sr Degree of Saturation (%)
w Moisture Content (%)
S Specific Gravity
e Void Ratio
D Dry Unit Weight (pcf)
D Unit Weight of Water (62.4 pcf)

GeoSystems
Engineering, Inc.

PERMEABILITY TEST RESULTS (ASTM 5084)

Project Name Industrial Services Job No. 951113
Date 11-30-95

Boring No. MW-88 Boring No. _____
Sample Type _____ Sample Type _____
Sample Depth 68-72' Sample Depth _____
Sample Description _____ Sample Description _____

	Before	After	Units		Before	After	Units
Moisture Content, w	22.9	25.6	%	Moisture Content, w			%
Dry Unit Weight, Dd	97.4	97.6	pcf	Dry Unit Weight, Dd			pcf
Height, L	3.97	3.97	inches	Height, L			inches
Diameter, d	2.80	2.80	inches	Diameter, d			inches
Degree of Saturation, Sr	84.7	95.2	%	Degree of Saturation, Sr			%
Applied Pressure (influent):		44.4	psi	Applied Pressure (influent):			psi
Applied Pressure (effluent):		43	psi	Applied Pressure (effluent):			psi
Hydraulic Gradient:		10		Hydraulic Gradient:			

Test Number		Time (sec)	Influent Reading	Effluent Reading	Test Number		Time (sec)	Influent Reading	Effluent Reading
1	Start	0	12.1	16.3	1	Start			
	Finish	54300	12.6	16.2		Finish			
2	Start	0	12.6	16.2	2	Start			
	Finish	104400	13.1	15.7		Finish			
3	Start	0	13.1	15.7	3	Start			
	Finish	166500	14.0	14.9		Finish			
4	Start	0	14.0	14.9	4	Start			
	Finish	74700	14.4	14.5		Finish			

Hydraulic Conductivity "K" (cm/sec)	1	1.4E-08	Hydraulic Conductivity "K" (cm/sec)	1
	2	1.2E-08		2
	3	1.3E-08		3
	4	1.4E-08		4
Avg. k		1.3E-08	Avg. k	

Assumed Specific Gravity, SG 2.70 Area of Tube, a 0.9721
Permeant: Deaired Tap Water

Formulas:

Permeability (Falling Head-Rising Tailwater Test)

$$k = (a^2 L / 2 A^2 t) \ln(h_0/h_1)$$

Degree of Saturation

$$Sr = w \cdot SG / e$$

$$Dd = (SG / (1 + e)) Dw$$

$$T \quad Sr = (w \cdot SG) / ((SG \cdot Dw / Dd) - 1)$$

F:\qpro\permnew.wq2 6/20/95

k Hydraulic Conductivity (cm/sec) Sr Degree of Saturation (%)
a Area of Tube (cm ^ 2) w Moisture Content (%)
L Height or Length of Sample (cm) S Specific Gravity
A Area of Sample (cm) e Void Ratio
t Time of Test Interval (sec) D Dry Unit Weight (pcf)
h0 Height of Head at Start of Test Interval (c D Unit Weight of Water (62.4 pcf)
h1 Height of Head at End of Test Interval (cm)

GeoSystems
Engineering, Inc.

APPENDIX 4

Soil Analytical Data

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
1633 South Marsh
Kansas City, MO 64126

REPORT #: 50726001-2

DATE: 10-5-95

ATTN: Brent Nickel

QAS #: 50726001

DATE SAMPLED: 7-26-95

SAMPLE IDENTIFICATION: Soil: MW8A-11.5'

DATE RECEIVED: 7-26-95


SAMPLED BY: Mick Cossairt

VOLATILE ORGANIC COMPOUNDS - SW-846-8260

PARAMETER	DET. LIMIT (ug/Kg)	CONC. (ug/Kg)
Acetone	250	: ND
* Acetonitrile	625	: ND
* Acrolein	625	: ND
* Acrylonitrile	125	: ND
* Allyl chloride	125	: ND
Benzene	65	: ND
Bromodichloromethane	65	: ND
Bromoform	65	: ND
Carbon disulfide	65	: ND
Carbon tetrachloride	65	: ND
Chlorobenzene	65	: ND
Chloroethane	65	: ND
Chloroform	65	: ND
* Chloroprene	125	: ND
Dibromochloromethane	65	: ND
1,2-Dibromo-3-chloropropane	125	: ND
1,2-Dibromoethane	125	: ND
* trans-1,4-Dichloro-2-butene	125	: ND
Dichlorodifluoromethane	125	: ND
1,1-Dichloroethane	65	: ND
1,2-Dichloroethane	65	: ND
1,1-Dichloroethene	65	: ND
trans-1,2-Dichloroethene	65	: ND
1,2-Dichloropropane	65	: ND
cis-1,3-Dichloropropene	65	: ND
trans-1,3-Dichloropropene	65	: ND
* 1,4-Dioxane	2,500	: ND

ND = NOT DETECTED

* TENTATIVELY IDENTIFIED COMPOUND


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
1633 South Marsh
Kansas City, MO 64126

REPORT #: 50726001-3

DATE: 10-5-95

ATTN: Brent Nickel

QAS #: 50726001

DATE RECEIVED: 7-26-95

DATE SAMPLED: 7-26-95

SAMPLED BY: Mick Cossairt


SAMPLE IDENTIFICATION: Soil: MW8A-11.5'

SEMI-VOLATILE ORGANIC COMPOUNDS - SW-846-8270

PARAMETER	DET. LIMIT (ug/Kg)	CONC. (ug/Kg)
Acenaphthene	500	: ND
Acenaphthylene	500	: ND
* Acetophenone	5,000	: ND
* 2-Acetylaminofluorene	5,000	: ND
* 4-Aminobiphenyl	5,000	: ND
* Aniline	5,000	: ND
Anthracene	500	: ND
* Aramite	10,000	: ND
Benzo(a)anthracene	500	: ND
Benzo(b)fluoranthene	500	: ND
Benzo(k)fluoranthene	500	: ND
Benzo(g,h,i)perylene	500	: ND
Benzo(a)pyrene	500	: ND
Benzyl alcohol	1,000	: ND
Bis(2-chloroethoxy)methane	500	: ND
Bis(2-chloroethyl)ether	500	: ND
Bis(2-chloroisopropyl)ether	500	: ND
Bis(2-ethylhexyl)phthalate	500	: ND
4-Bromophenyl phenyl ether	500	: ND
Butyl benzyl phthalate	500	: ND
4-Chloroaniline	1,000	: ND
* Chlorobenzilate	5,000	: ND
4-Chloro-3-methylphenol	1,000	: ND
2-Chloronaphthalene	500	: ND
2-Chlorophenol	500	: ND
4-Chlorophenyl phenyl ether	500	: ND
Chrysene	500	: ND
3-Methylphenol	500	: ND

ND = NOT DETECTED

* TENTATIVELY IDENTIFIED COMPOUND


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
| Kansas City, MO

REPORT #: 50726001-3

DATE: 10-5-95

ATTN: Brent Nickel

- PAGE 2 -

SEMI-VOLATILE ORGANIC COMPOUNDS - SW-846-8270

PARAMETER	DET. LIMIT (ug/Kg)	CONC. (ug/Kg)
2-Methylphenol	500	: ND
4-Methylphenol	500	: ND
* Diallate	5,000	: ND
Dibenz(a,h)anthracene	500	: ND
Dibenzofuran	500	: ND
Di-n-butyl phthalate	500	: ND
1,2-Dichlorobenzene	500	: ND
1,3-Dichlorobenzene	500	: ND
1,4-Dichlorobenzene	500	: ND
3,3'-Dichlorobenzidine	1,000	: ND
2,4-Dichlorophenol	500	: ND
* 2,6-Dichlorophenol	5,000	: ND
Diethyl phthalate	500	: ND
* Thionazin	5,000	: ND
* Dimethoate	5,000	: ND
* p-(Dimethylamino)azobenzene	5,000	: ND
* 7,12-Dimethylbenz(a)anthracene	5,000	: ND
* 3,3'-Dimethylbenzidine	5,000	: ND
* a,a-Dimethylphenethylamine	1,000	: ND
2,4-Dimethylphenol	500	: ND
Dimethyl phthalate	500	: ND
* 1,3-Dinitrobenzene	5,000	: ND
2-Methyl-4,6-dinitrophenol	2,500	: ND
2,4-Dinitrophenol	2,500	: ND
2,4-Dinitrotoluene	500	: ND
2,6-Dinitrotoluene	500	: ND
Di-n-octyl phthalate	500	: ND
* Diphenylamine	1,000	: ND
* Disulfoton	5,000	: ND
* Ethyl methanesulfonate	5,000	: ND

ND = NOT DETECTED

* TENTATIVELY IDENTIFIED COMPOUND


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
| Kansas City, MO

REPORT #: 50726001-3

DATE: 10-5-95

ATTN: Brent Nickel


- PAGE 3 -

SEMI-VOLATILE ORGANIC COMPOUNDS - SW-846-8270

PARAMETER	DET. LIMIT (ug/Kg)	CONC. (ug/Kg)
* Camphur	10,000	: ND
Fluoranthene	500	: ND
Fluorene	500	: ND
Hexachlorobutadiene	500	: ND
Hexachlorocyclopentadiene	500	: ND
Hexachloroethane	500	: ND
* Hexachlorophene	50,000	: ND
* Hexachloropropene	5,000	: ND
Indeno(1,2,3-cd)pyrene	500	: ND
* Isodrin	5,000	: ND
Isophorone	500	: ND
* Isosafrole	5,000	: ND
* Kepone	10,000	: ND
* Methapyrilene	5,000	: ND
* 3-Methylcholanthrene	5,000	: ND
* Methyl methanesulfonate	5,000	: ND
2-Methylnaphthalene	500	: ND
* Methyl parathion	5,000	: ND
Naphthalene	500	: ND
* 1,4-Naphthoquinone	5,000	: ND
* 1-Naphthylamine	5,000	: ND
* 2-Naphthylamine	5,000	: ND
2-Nitroaniline	2,500	: ND
3-Nitroaniline	2,500	: ND
4-Nitroaniline	2,500	: ND
Nitrobenzene	500	: ND
2-Nitrophenol	500	: ND
4-Nitrophenol	2,500	: ND
* 4-Nitroquinoline 1-oxide	10,000	: ND
* N-Nitrosodi-n-butylamine	5,000	: ND
* N-Nitrosodiethylamine	5,000	: ND

ND = NOT DETECTED

* TENTATIVELY IDENTIFIED COMPOUND


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
| Kansas City, MO

REPORT #: 50726001-3

DATE: 10-5-95

ATTN: Brent Nickel


- PAGE 4 -

SEMI-VOLATILE ORGANIC COMPOUNDS - SW-846-8270

PARAMETER	DET. LIMIT (ug/Kg)	CONC. (ug/Kg)
* N-Nitrosodimethylamine	5,000	: ND
N-Nitrosodiphenylamine	500	: ND
N-Nitrosodipropylamine	500	: ND
* N-Nitrosomethylethylamine	5,000	: ND
* N-Nitrosomorpholine	5,000	: ND
* N-Nitrosopiperidine	5,000	: ND
* N-Nitrosopyrrolidine	5,000	: ND
* 5-Nitro-o-toluidine	5,000	: ND
* Parathion	5,000	: ND
* Pentachlorobenzene	5,000	: ND
* Pentachloronitrobenzene	5,000	: ND
Pentachlorophenol	2,500	: ND
* Phenacetin	5,000	: ND
Phenanthrene	500	: ND
Phenol	500	: ND
* p-Phenylenediamine	50,000	: ND
* Phorate	5,000	: ND
* 2-Picoline	1,000	: ND
* Pronamide	5,000	: ND
Pyrene	500	: ND
* Pyridine	10,000	: ND
* Safrole	5,000	: ND
* 1,2,4,5-Tetrachlorobenzene	5,000	: ND
* 2,3,4,6-Tetrachlorophenol	5,000	: ND
* Tetraethyl dithiopyrophosphate	5,000	: ND
* o-Toluidine	1,000	: ND
1,2,4-Trichlorobenzene	500	: ND
2,4,5-Trichlorophenol	500	: ND
2,4,6-Trichlorophenol	500	: ND
* O,O,O-Triethyl phosphorothioate	5,000	: ND
* sym-Trinitrobenzene	5,000	: ND

ND = NOT DETECTED

* TENTATIVELY IDENTIFIED COMPOUND


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
1633 South Marsh
Kansas City, MO 64126

REPORT #: 50726001-1

DATE: 10-5-95

ATTN: Brent Nickel

QAS #: 50726001

DATE SAMPLED: 7-26-95

SAMPLE IDENTIFICATION: Soil: MW8A-11.5'

DATE RECEIVED: 7-26-95

SAMPLED BY: Mick Cossairt

PARAMETER	METHOD	DET. LIMIT	CONC.
Total Metals	SW-846-3050	(mg/Kg)	: (mg/Kg)
Antimony	SW-846-6010	3.0	: ND
Arsenic	SW-846-6010	5.0	: 5.62
Barium	SW-846-6010	2.0	: 155
Beryllium	SW-846-6010	0.05	: 0.521
Cadmium	SW-846-6010	0.25	: ND
Chromium	SW-846-6010	0.4	: 9.64
Cobalt	SW-846-6010	0.05	: 5.16
Copper	SW-846-6010	0.45	: 9.56
Lead	SW-846-6010	5.0	: 7.64
Mercury	SW-846-7471	0.075	: ND
Nickel	SW-846-6010	0.75	: 15.2
Selenium	SW-846-6010	5.0	: ND
Silver	SW-846-6010	2.5	: ND
Thallium	SW-846-7841	0.185	: ND
Tin	SW-846-6010	2.5	: ND
Vanadium	SW-846-6010	0.7	: 28.6
Zinc	SW-846-6010	0.4	: 43.3
Cyanide, Total	SW-846-9010	0.25 mg/Kg	: ND
Sulfide, Total	SW-846-9030	2.5 mg/Kg	: ND

ND = NOT DETECTED
NA = NOT APPLICABLE


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50726001-5

DATE: 10-5-95

ATTN: Brent Nickel

QAS #: 50726001

DATE RECEIVED: 7-26-95


DATE SAMPLED: 7-26-95

SAMPLED BY: Mick Cossairt

SAMPLE IDENTIFICATION: Soil - MW8A-11.5'

PARAMETER	METHOD	DET. LIMIT	CONC.
:	:	:	:
: CHLORINATED	:	: (ug/Kg)	: (ug/Kg)
: HERBICIDES	:	:	:
:	:	:	:
: 2,4-D	: SW-846-8150	: 4.0	: ND
:	:	:	:
: 2,4,5-T	: SW-846-8150	: 2.0	: ND
:	:	:	:
: 2,4,5-TP (Silvex)	: SW-846-8150	: 2.0	: ND
:	:	:	:
: Dinoseb	: SW-846-8150	: 2.0	: ND
:	:	:	:
:	:	:	:
:	:	:	:
:	:	:	:
:	:	:	:
:	:	:	:
:	:	:	:
:	:	:	:
:	:	:	:

ND = NOT DETECTED
NA = NOT APPLICABLE


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126

REPORT #: 50726001-4

DATE: 10-5-95

ATTN: Brent Nickel

QAS #: 50726001

DATE RECEIVED: 7-26-95

DATE SAMPLED: 7-26-95


SAMPLED BY: Mick Cossairt

SAMPLE IDENTIFICATION: Soil: MW8A-11.5'

PESTICIDES AND PCBS - SW-846-8080


PARAMETER	DET. LIMIT (ug/Kg)	CONC. (ug/Kg)
Aldrin	: 5.4	: ND
alpha-BHC	: 4.0	: ND
beta-BHC	: 8.0	: ND
delta-BHC	: 12.0	: ND
gamma-BHC	: 5.4	: ND
Chlordane	: 18.8	: ND
4,4'-DDD	: 14.8	: ND
4,4'-DDE	: 5.4	: ND
4,4'-DDT	: 16.0	: ND
Dieldrin	: 2.6	: ND
Endosulfan I	: 18.8	: ND
Endosulfan II	: 5.4	: ND
Endosulfan sulfate	: 88.4	: ND
Endrin	: 8.0	: ND
Endrin aldehyde	: 30.8	: ND
Heptachlor	: 4.0	: ND
Heptachlor epoxide	: 111	: ND
Hexachlorobenzene	: 68.0	: ND
Methoxychlor	: 236	: ND
Toxaphene	: 322	: ND
PCB-1016	: 87.2	: ND
PCB-1221	: 87.2	: ND
PCB-1232	: 87.2	: ND
PCB-1242	: 87.2	: ND
PCB-1248	: 87.2	: ND
PCB-1254	: 174	: ND
PCB-1260	: 174	: ND

ND = NOT DETECTED


Norman L. Cunningham

APPENDIX 5

Waste Authorization and Soil Analytical Data



Johnson County
Kansas

November 14, 1995

RECEIVED
NOV 15 1995
ENGINEERING DEPT.

DT

Mr. Sean White
Manager, Legislature & Regulatory Affairs
ISC
1633 S. Marsh, P.O. Box 266219
Kansas City, Missouri 64126

Re: Johnson County Industrial Solid Waste Disposal Authorization Number 95-234

Dear Mr. White:

We are in receipt of your letter of November 2, 1995, requesting to dispose of approximately five cubic yards of soil cuttings. Information you supplied indicated the waste is non-hazardous.

Approval is given to dispose of this waste at the Johnson County Landfill, Inc., operating under Kansas Permit 263 and Johnson County Permit No. 95-02, provided the following conditions are met:

1. Approval to deliver the waste must be obtained from the landfill operator prior to transporting the waste to the landfill. The final decision on whether to accept or reject the waste rests with the landfill operator. Please call Mr. Dan Taylor, 913/631-3300 to obtain approval. If the landfill operator refuses to accept this waste you should contact us to determine alternative disposal options.
2. The waste must be transported separately to the landfill and be identified to the operator upon delivery.
3. Kansas Administrative Regulation 28-29-108(12) requires solid waste disposal facilities to maintain a log of commercial or industrial solid wastes received including sludges, barreled wastes and special wastes. The log shall indicate the source and quantity of waste and the disposal location. The industrial waste authorization number should be used as identification when entering the shipment into the log.
4. Sludges must be adequately containerized to prevent spillage of waste on roads and highways during transportation.



Solid Waste Disposal Authorization #95-234
November 14, 1995
Page 2

5. This approval is valid for a one-time shipment only of this waste to the landfill. This authorization expires November 14, 1996. If the waste has not been taken to the landfill by this date, you must apply for a new authorization.

If you have any questions, please contact Inna Prilutsky of this office.

Sincerely,


Philip J. Wittek
Director

PJW:IP:cw/SWST1/95-234.swd

c: Richard Bronaugh, Kansas Department of Health and Environment
Inna Prilutsky, Environmental Programs Coordinator
Dan Taylor, Johnson County Landfill, Inc.

RECEIVED

NOV 10 1995

ENVIRONMENTAL DEPT.

JOHNSON COUNTY ENVIRONMENTAL DEPARTMENT

11180 Thompson Avenue
Southlake Tech Center, Building #4
Lenexa, Kansas 66219

SPECIAL WASTE DISPOSAL REQUEST FORM

I. General Information

Company Name	TSC
Address	1633 S. Marsh, PO Box 266219
City, State, Zip	Kansas City, MO 64126
Contact, Title	Sean White, Director of Republican Initiatives
Telephone Number	(913) 631-3300

Initiation
needed
for

II. Waste Characterization

A. Name of Waste: Soil CuttingsB. Description of Waste Generation Process: Soil from installation of monitoring wellsC. Physical State: (Check One) 1-Solid ☒ 2-Slurry ☐ 3-Liquid ☐ 4-Sludge ☐ 5-Other (Specify) ☐Waste Physical Properties: pH ☐ % Solids By Weight ☐ Flash Point ☐ Using Pensky-Martins
Closed Cup (ASTM D-93-77) or Setflash Closed Tester (ASTM D-3278-73) Special Gravity ☐
Odor Description ☐ Free Fluid: Yes ☐ No ☒D. Was the waste ever classified or listed as hazardous? NOIf Yes, the previous waste I.D. number was ☐

E. Chemical Composition (attach any additional analysis with description of sampling and analytical methods, and all applicable Material Safety Data Sheets). Lab analysis cannot be older than one (1) year to be used here. All analyses performed by or for the waste generator shall be performed in accordance with standard laboratory methods and performed by a laboratory certified by the Kansas Department of Health and Environment for the required parameters, utilizing Environmental Protection Agency approved methodologies, 40 CFR 136.

Major Components - Weight %

1	see attached	4	
2	analysis	5	
3		6	

F. Source of Chemical Data: Quality analytical services

III. Disposal Rate

Waste Disposal will be: (Check One)

A. Continual _____ Average Disposal Rate Per Month _____ Include Units

B. Intermittent _____ Rate _____ Include Units

C. One Time Only X Quantity 5.0 Include Units yd³

D. If A or B, indicate amount for immediate disposal _____

IV. Transportation

A. Container Used for Transportation (Check One)

1. _____ Bulk (_____ cubic yards)

2. X Metal Drum (55 gallons)

3. _____ Cases, Cartons (size, number/case _____)

4. _____ Fiber Drums (_____ gallons)

5. Other (Specify) _____

B. Will the container used in transport be landfilled with the waste? yes

If No, specify _____

V. Certification

I, the undersigned, submit this request to dispose of the named waste and certify that the waste named herein to the best of my knowledge is not a hazardous waste as defined by the state(s) in which it is generated, transported, and/or stored, including the Kansas Hazardous Waste Management Regulations, and that the information supplied by me is correct. I also understand that if a disposal authorization is issued will be valid for one (1) year from the date of issue.

Signature of Waste Generator*	<u>Sean White</u>
Print Name	<u>Sean White</u>
Title	<u>Director of Republican Initiatives</u>
Date	<u>11-2-95</u>

Correction needed

Additional Comments:

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823006-1

DATE: 10-17-95


ATTN: Brent Nickel

QAS #: 50823006
DATE SAMPLED: 8-23-95
SAMPLE IDENTIFICATION: Soil - #1

DATE RECEIVED: 8-23-95
SAMPLED BY: Mick Cossairt

PARAMETER	METHOD	DET. LIMIT (mg/L)	CONC. (mg/L)
TCLP - Metals	SW-1311		
Arsenic	SW-6010	0.1	: ND
Barium	SW-6010	0.04	: 1.18
Cadmium	SW-6010	0.005	: ND
Chromium	SW-6010	0.008	: ND
Lead	SW-6010	0.1	: ND
Mercury	SW-7470	0.0003	: ND
Selenium	SW-6010	0.1	: ND
Silver	SW-6010	0.05	: ND

ND = NOT DETECTED


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823006-3

DATE: 10-17-95

ATTN: Brent Nickel


QAS #: 50823006
DATE SAMPLED: 8-23-95
SAMPLE IDENTIFICATION: Soil - #1

DATE RECEIVED: 8-23-95
SAMPLED BY: Mick Cossairt

(TCLP) SEMI-VOLATILE ORGANIC COMPOUNDS - SW-846-1311/8270

PARAMETER	DET. LIMIT (mg/L)	CONC. (mg/L)
o-Cresol (2-Methylphenol)	: 0.025	: ND
m-Cresol (3-Methylphenol)	: 0.025	: ND
p-Cresol (4-Methylphenol)	: 0.025	: ND
Cresol (Total)	: 0.025	: ND
1,4-Dichlorobenzene	: 0.025	: ND
2,4-Dinitrotoluene	: 0.025	: ND
Hexachlorobenzene	: 0.025	: ND
Hexachloro-1,3-butadiene	: 0.025	: ND
Hexachloroethane	: 0.025	: ND
Nitrobenzene	: 0.025	: ND
Pentachlorophenol	: 0.125	: ND
Pyridine	: 5.00	: ND
2,4,5-Trichlorophenol	: 0.025	: ND
2,4,6-Trichlorophenol	: 0.025	: ND

ND = NOT DETECTED


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823006-4

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823006
DATE SAMPLED: 8-23-95
SAMPLE IDENTIFICATION: Soil - #1


DATE RECEIVED: 8-23-95
SAMPLED BY: Mick Cossairt

PCBS - SW-846-8080

PARAMETER	DET. LIMIT (ug/Kg)	CONC. (ug/Kg)
PCB-1016	: 50	: ND
PCB-1221	: 50	: ND
PCB-1232	: 50	: ND
PCB-1242	: 50	: ND
PCB-1248	: 50	: ND
PCB-1254	: 50	: ND
PCB-1260	: 50	: ND

ND = NOT DETECTED


Norman L. Cunningham


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823007-1

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823007
DATE SAMPLED: 8-23-95
SAMPLE IDENTIFICATION: Soil - #2

DATE RECEIVED: 8-23-95
SAMPLED BY: Mick Cossairt

PARAMETER	METHOD	DET. LIMIT (mg/L)	CONC. (mg/L)
TCLP - Metals	SW-1311		
Arsenic	SW-6010	0.1	: ND
Barium	SW-6010	0.04	: 1.66
Cadmium	SW-6010	0.005	: ND
Chromium	SW-6010	0.008	: ND
Lead	SW-6010	0.1	: ND
Mercury	SW-7470	0.0003	: ND
Selenium	SW-6010	0.1	: ND
Silver	SW-6010	0.05	: ND

ND = NOT DETECTED


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823007-2

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823007
DATE SAMPLED: 8-23-95
SAMPLE IDENTIFICATION: Soil - #2

DATE RECEIVED: 8-23-95
SAMPLED BY: Mick Cossairt

(TCLP) VOLATILE ORGANIC COMPOUNDS - SW-846-1311/8260

PARAMETER	DET. LIMIT (mg/L)	CONC. (mg/L)
Benzene	: 0.00313	: ND
Carbon tetrachloride	: 0.00313	: ND
Chlorobenzene	: 0.00313	: ND
Chloroform	: 0.00313	: ND
1,2-Dichloroethane	: 0.00313	: ND
1,1-Dichloroethylene	: 0.00313	: ND
Methyl ethyl ketone (2-Butanone)	: 0.0125	: ND
Tetrachloroethylene	: 0.00313	: ND
Trichloroethylene	: 0.00313	: ND
Vinyl chloride	: 0.00125	: ND

ND = NOT DETECTED


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823007-3

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823007

DATE SAMPLED: 8-23-95

SAMPLE IDENTIFICATION: Soil - #2

DATE RECEIVED: 8-23-95

SAMPLED BY: Mick Cossairt

(TCLP) SEMI-VOLATILE ORGANIC COMPOUNDS - SW-846-1311/8270

PARAMETER	DET. LIMIT (mg/L)	CONC. (mg/L)
o-Cresol (2-Methylphenol)	: 0.025	: ND
m-Cresol (3-Methylphenol)	: 0.025	: ND
p-Cresol (4-Methylphenol)	: 0.025	: ND
Cresol (Total)	: 0.025	: ND
1,4-Dichlorobenzene	: 0.025	: ND
2,4-Dinitrotoluene	: 0.025	: ND
Hexachlorobenzene	: 0.025	: ND
Hexachloro-1,3-butadiene	: 0.025	: ND
Hexachloroethane	: 0.025	: ND
Nitrobenzene	: 0.025	: ND
Pentachlorophenol	: 0.125	: ND
Pyridine	: 5.00	: ND
2,4,5-Trichlorophenol	: 0.025	: ND
2,4,6-Trichlorophenol	: 0.025	: ND

ND = NOT DETECTED


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823007-4

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823007

DATE SAMPLED: 8-23-95

SAMPLE IDENTIFICATION: Soil - #2


DATE RECEIVED: 8-23-95


SAMPLED BY: Mick Cossairt

PCBS - SW-846-8080

PARAMETER	DET. LIMIT (ug/Kg)	CONC. (ug/Kg)
PCB-1016	: 50	: ND
PCB-1221	: 50	: ND
PCB-1232	: 50	: ND
PCB-1242	: 50	: ND
PCB-1248	: 50	: ND
PCB-1254	: 50	: ND
PCB-1260	: 50	: ND

ND = NOT DETECTED


Norman L. Cunningham


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823008-1

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823008
DATE SAMPLED: 8-23-95
SAMPLE IDENTIFICATION: Soil - #3

DATE RECEIVED: 8-23-95
SAMPLED BY: Mick Cossairt

PARAMETER	METHOD	DET. LIMIT (mg/L)	CONC. (mg/L)
TCLP - Metals	SW-1311		
Arsenic	SW-6010	0.1	: ND
Barium	SW-6010	0.04	: 1.29
Cadmium	SW-6010	0.005	: 0.0084
Chromium	SW-6010	0.008	: ND
Lead	SW-6010	0.1	: ND
Mercury	SW-7470	0.0003	: ND
Selenium	SW-6010	0.1	: ND
Silver	SW-6010	0.05	: 0.0577

ND = NOT DETECTED


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823008-2

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823008

DATE RECEIVED: 8-23-95

DATE SAMPLED: 8-23-95

SAMPLED BY: Mick Cossairt

SAMPLE IDENTIFICATION: Soil - #3

(TCLP) VOLATILE ORGANIC COMPOUNDS - SW-846-1311/8260

PARAMETER	DET. LIMIT (mg/L)	CONC. (mg/L)
Benzene	: 0.00313	: ND
Carbon tetrachloride	: 0.00313	: ND
Chlorobenzene	: 0.00313	: ND
Chloroform	: 0.00313	: ND
1,2-Dichloroethane	: 0.00313	: ND
1,1-Dichloroethylene	: 0.00313	: ND
Methyl ethyl ketone (2-Butanone)	: 0.0125	: ND
Tetrachloroethylene	: 0.00313	: ND
Trichloroethylene	: 0.00313	: ND
Vinyl chloride	: 0.00125	: ND

ND = NOT DETECTED


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823008-3

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823008
DATE SAMPLED: 8-23-95
SAMPLE IDENTIFICATION: Soil - #3

DATE RECEIVED: 8-23-95
SAMPLED BY: Mick Cossairt

(TCLP) SEMI-VOLATILE ORGANIC COMPOUNDS - SW-846-1311/8270

PARAMETER	DET. LIMIT (mg/L)	CONC. (mg/L)
o-Cresol (2-Methylphenol)	: 0.025	: ND
m-Cresol (3-Methylphenol)	: 0.025	: ND
p-Cresol (4-Methylphenol)	: 0.025	: ND
Cresol (Total)	: 0.025	: ND
1,4-Dichlorobenzene	: 0.025	: ND
2,4-Dinitrotoluene	: 0.025	: ND
Hexachlorobenzene	: 0.025	: ND
Hexachloro-1,3-butadiene	: 0.025	: ND
Hexachloroethane	: 0.025	: ND
Nitrobenzene	: 0.025	: ND
Pentachlorophenol	: 0.125	: ND
Pyridine	: 5.00	: ND
2,4,5-Trichlorophenol	: 0.025	: ND
2,4,6-Trichlorophenol	: 0.025	: ND

ND = NOT DETECTED


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823008-4

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823008

DATE RECEIVED: 8-23-95

DATE SAMPLED: 8-23-95

SAMPLED BY: Mick Cossairt

SAMPLE IDENTIFICATION: Soil - #3

PCBS - SW-846-8080

PARAMETER	DET. LIMIT (ug/Kg)	CONC. (ug/Kg)
PCB-1016	: 50	: ND
PCB-1221	: 50	: ND
PCB-1232	: 50	: ND
PCB-1242	: 50	: ND
PCB-1248	: 50	: ND
PCB-1254	: 50	: ND
PCB-1260	: 50	: ND

ND = NOT DETECTED


Norman L. Cunningham

Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823009-1

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823009

DATE RECEIVED: 8-23-95


DATE SAMPLED: 8-23-95

SAMPLED BY: Mick Cossairt

SAMPLE IDENTIFICATION: Soil - #4

PARAMETER	METHOD	DET. LIMIT (mg/L)	CONC. (mg/L)
TCLP - Metals	SW-1311		
Arsenic	SW-6010	0.1	: ND
Barium	SW-6010	0.04	: 1.74
Cadmium	SW-6010	0.005	: ND
Chromium	SW-6010	0.008	: ND
Lead	SW-6010	0.1	: ND
Mercury	SW-7470	0.0003	: ND
Selenium	SW-6010	0.1	: ND
Silver	SW-6010	0.05	: 0.0589

ND = NOT DETECTED


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823009-2

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823009

DATE RECEIVED: 8-23-95

DATE SAMPLED: 8-23-95

SAMPLED BY: Mick Cossairt

SAMPLE IDENTIFICATION: Soil - #4

(TCLP) VOLATILE ORGANIC COMPOUNDS - SW-846-1311/8260

PARAMETER	DET. LIMIT (mg/L)	CONC. (mg/L)
Benzene	: 0.00313	: ND
Carbon tetrachloride	: 0.00313	: ND
Chlorobenzene	: 0.00313	: ND
Chloroform	: 0.00313	: ND
1,2-Dichloroethane	: 0.00313	: ND
1,1-Dichloroethylene	: 0.00313	: ND
Methyl ethyl ketone (2-Butanone)	: 0.0125	: ND
Tetrachloroethylene	: 0.00313	: ND
Trichloroethylene	: 0.00313	: ND
Vinyl chloride	: 0.00125	: ND

ND = NOT DETECTED


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 235-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT # 50823009-3

DATE: 11-17-95

ATTN: Brent Nickel

QAS #: 50823009
DATE SAMPLED: 8-23-95
SAMPLE IDENTIFICATION: Soil - #4

DATE RECEIVED: 8-23-95
SAMPLED BY: Mick Cossairt

(TCLP) SEMI-VOLATILE ORGANIC COMPOUNDS - SW-846-1311/8270

PARAMETER	DET. LIMIT (mg/L)	CONC. (mg/L)
o-Cresol (2-Methylphenol)	: 0.025	: ND
m-Cresol (3-Methylphenol)	: 0.025	: ND
p-Cresol (4-Methylphenol)	: 0.025	: ND
Cresol (Total)	: 0.025	: ND
1,4-Dichlorobenzene	: 0.025	: ND
2,4-Dinitrotoluene	: 0.025	: ND
Hexachlorobenzene	: 0.025	: ND
Hexachloro-1,3-butadiene	: 0.025	: ND
Hexachloroethane	: 0.025	: ND
Nitrobenzene	: 0.025	: ND
Pentachlorophenol	: 0.125	: ND
Pyridine	: 5.00	: ND
2,4,5-Trichlorophenol	: 0.025	: ND
2,4,6-Trichlorophenol	: 0.025	: ND

ND = NOT DETECTED


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823009-4

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823009

DATE RECEIVED: 8-23-95

DATE SAMPLED: 8-23-95

SAMPLED BY: Mick Cossairt

SAMPLE IDENTIFICATION: Soil - #4

PCBS - SW-846-8080

PARAMETER	DET. LIMIT (ug/Kg)	CONC. (ug/Kg)
PCB-1016	: 50	: ND
PCB-1221	: 50	: ND
PCB-1232	: 50	: ND
PCB-1242	: 50	: ND
PCB-1248	: 50	: ND
PCB-1254	: 50	: ND
PCB-1260	: 50	: ND

ND = NOT DETECTED


Norman L. Cunningham

Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823010-1

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823010

DATE SAMPLED: 8-23-95

SAMPLE IDENTIFICATION: Soil - #5

DATE RECEIVED: 8-23-95

SAMPLED BY: Mick Cossairt

PARAMETER	METHOD	DET. LIMIT (mg/L)	CONC. (mg/L)
TCLP - Metals	SW-1311		
Arsenic	SW-6010	0.1	: ND
Barium	SW-6010	0.04	: 1.81
Cadmium	SW-6010	0.005	: ND
Chromium	SW-6010	0.008	: ND
Lead	SW-6010	0.1	: ND
Mercury	SW-7470	0.0003	: ND
Selenium	SW-6010	0.1	: ND
Silver	SW-6010	0.05	: 0.0610

ND = NOT DETECTED


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823010-2

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823010
DATE SAMPLED: 8-23-95
SAMPLE IDENTIFICATION: Soil - #5

DATE RECEIVED: 8-23-95
SAMPLED BY: Mick Cossairt

(TCLP) VOLATILE ORGANIC COMPOUNDS - SW-846-1311/8260

PARAMETER	DET. LIMIT (mg/L)	CONC. (mg/L)
Benzene	: 0.00313	: ND
Carbon tetrachloride	: 0.00313	: ND
Chlorobenzene	: 0.00313	: ND
Chloroform	: 0.00313	: ND
1,2-Dichloroethane	: 0.00313	: ND
1,1-Dichloroethylene	: 0.00313	: ND
Methyl ethyl ketone (2-Butanone)	: 0.0125	: ND
Tetrachloroethylene	: 0.00313	: ND
Trichloroethylene	: 0.00313	: ND
Vinyl chloride	: 0.00125	: ND

ND = NOT DETECTED


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823010-3

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823010
DATE SAMPLED: 8-23-95
SAMPLE IDENTIFICATION: Soil - #5

DATE RECEIVED: 8-23-95
SAMPLED BY: Mick Cossairt

(TCLP) SEMI-VOLATILE ORGANIC COMPOUNDS - SW-846-1311/8270

PARAMETER	DET. LIMIT (mg/L)	CONC. (mg/L)
o-Cresol (2-Methylphenol)	: 0.025	: ND
m-Cresol (3-Methylphenol)	: 0.025	: ND
p-Cresol (4-Methylphenol)	: 0.025	: ND
Cresol (Total)	: 0.025	: ND
1,4-Dichlorobenzene	: 0.025	: ND
2,4-Dinitrotoluene	: 0.025	: ND
Hexachlorobenzene	: 0.025	: ND
Hexachloro-1,3-butadiene	: 0.025	: ND
Hexachloroethane	: 0.025	: ND
Nitrobenzene	: 0.025	: ND
Pentachlorophenol	: 0.125	: ND
Pyridine	: 5.00	: ND
2,4,5-Trichlorophenol	: 0.025	: ND
2,4,6-Trichlorophenol	: 0.025	: ND

ND = NOT DETECTED


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823010-4

DATE: 10-17-95

ATTN: Brent Nickel


QAS #: 50823010
DATE SAMPLED: 8-23-95
SAMPLE IDENTIFICATION: Soil - #5

DATE RECEIVED: 8-23-95
SAMPLED BY: Mick Cossairt

PCBS - SW-846-8080

PARAMETER	DET. LIMIT (ug/Kg)	CONC. (ug/Kg)
PCB-1016	: 50	: ND
PCB-1221	: 50	: ND
PCB-1232	: 50	: ND
PCB-1242	: 50	: ND
PCB-1248	: 50	: ND
PCB-1254	: 50	: ND
PCB-1260	: 50	: ND

ND = NOT DETECTED


Norman L. Cunningham

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823010-5

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823010
DATE SAMPLED: 8-23-95
SAMPLE IDENTIFICATION: Soil - #5

DATE RECEIVED: 8-23-95

SAMPLED BY: Mick Cossairt

[illegible]

ND = NOT DETECTED
NA = NOT APPLICABLE

Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823011-1

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823011

DATE SAMPLED: 8-23-95


SAMPLE IDENTIFICATION: Soil - #6

DATE RECEIVED: 8-23-95

SAMPLED BY: Mick Cossairt

PARAMETER	METHOD	DET. LIMIT (mg/L)	CONC. (mg/L)
TCLP - Metals	SW-1311		
Arsenic	SW-6010	0.1	: ND
Barium	SW-6010	0.04	: 1.54
Cadmium	SW-6010	0.005	: ND
Chromium	SW-6010	0.008	: ND
Lead	SW-6010	0.1	: ND
Mercury	SW-7470	0.0003	: ND
Selenium	SW-6010	0.1	: ND
Silver	SW-6010	0.05	: 0.0625

ND = NOT DETECTED


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823011-2

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823011

DATE RECEIVED: 8-23-95

DATE SAMPLED: 8-23-95

SAMPLED BY: Mick Cossairt

SAMPLE IDENTIFICATION: Soil - #6

(TCLP) VOLATILE ORGANIC COMPOUNDS - SW-846-1311/8260

PARAMETER	DET. LIMIT (mg/L)	CONC. (mg/L)
Benzene	: 0.00313	: ND
Carbon tetrachloride	: 0.00313	: ND
Chlorobenzene	: 0.00313	: ND
Chloroform	: 0.00313	: ND
1,2-Dichloroethane	: 0.00313	: ND
1,1-Dichloroethylene	: 0.00313	: ND
Methyl ethyl ketone (2-Butanone)	: 0.0125	: ND
Tetrachloroethylene	: 0.00313	: ND
Trichloroethylene	: 0.00313	: ND
Vinyl chloride	: 0.00125	: ND

ND = NOT DETECTED


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823011-3

DATE: 10-17-95

ATTN: Brent Nickel


QAS #: 50823011
DATE SAMPLED: 8-23-95
SAMPLE IDENTIFICATION: Soil - #6

DATE RECEIVED: 8-23-95
SAMPLED BY: Mick Cossairt

(TCLP) SEMI-VOLATILE ORGANIC COMPOUNDS - SW-846-1311/8270

PARAMETER	DET. LIMIT (mg/L)	CONC. (mg/L)
o-Cresol (2-Methylphenol)	: 0.025	: ND
m-Cresol (3-Methylphenol)	: 0.025	: ND
p-Cresol (4-Methylphenol)	: 0.025	: ND
Cresol (Total)	: 0.025	: ND
1,4-Dichlorobenzene	: 0.025	: ND
2,4-Dinitrotoluene	: 0.025	: ND
Hexachlorobenzene	: 0.025	: ND
Hexachloro-1,3-butadiene	: 0.025	: ND
Hexachloroethane	: 0.025	: ND
Nitrobenzene	: 0.025	: ND
Pentachlorophenol	: 0.125	: ND
Pyridine	: 5.00	: ND
2,4,5-Trichlorophenol	: 0.025	: ND
2,4,6-Trichlorophenol	: 0.025	: ND

ND = NOT DETECTED


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823011-4

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823011

DATE SAMPLED: 8-23-95

SAMPLE IDENTIFICATION: Soil - #6

DATE RECEIVED: 8-23-95

SAMPLED BY: Mick Cossairt

PCBS - SW-846-8080

PARAMETER	DET. LIMIT (ug/Kg)	CONC. (ug/Kg)
PCB-1016	: 50	: ND
PCB-1221	: 50	: ND
PCB-1232	: 50	: ND
PCB-1242	: 50	: ND
PCB-1248	: 50	: ND
PCB-1254	: 50	: ND
PCB-1260	: 50	: ND

ND = NOT DETECTED


Norman L. Cunningham

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823011-5

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823011
DATE SAMPLED: 8-23-95
SAMPLE IDENTIFICATION: Soil - #6

DATE RECEIVED: 8-23-95
SAMPLED BY: Mick Cossairt

[illegible]

ND = NOT DETECTED
NA = NOT APPLICABLE

Norman L. Cunningham

FACSIMILE COVER PAGE

Deffenbaugh Industries, Inc.
P.O. Box 3220
Shawnee, KS 66203

(913) 631-3300
FAX 631-3996

Date: 11/13/95

To: Inna Prilutsky
SCED

FAX #: 492-0142

From: Sean White
Internet E-mail: swhite@fileshop.com

Total Pages: 2
(Including cover page)

If all pages are not received, call (913) 631-3300 ext. 130

Message:

Inna,

*You were correct - it appears that I have
fallen victim to the shenanigans of
an office prankster. As we discussed,
I've attached a corrected signature page.*

Sean

This message is intended only for the use of the individual or entity to which it is addressed, and may contain information that is privileged, confidential and exempt from disclosure under applicable law. If the reader of this message is not the intended recipient, or the employee or agent responsible for delivering the message to the intended recipient, you are hereby notified that any dissemination, distribution or copying of this communication is strictly prohibited. If you have received this communication in error, please notify the sender immediately by telephone, and return the original message to the above address via the U.S. Postal Service. Thank you.

APPENDIX 6

Waste Water Analytical Data

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823005-1

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823005

DATE RECEIVED: 8-23-95

DATE SAMPLED: 8-23-95

SAMPLED BY: Mick Cossairt

SAMPLE IDENTIFICATION: Water - Decon Water

PARAMETER	METHOD	DET. LIMIT (mg/L)	CONC. (mg/L)
TCLP - Metals	SW-1311		
Arsenic	SW-6010	0.1	: ND
Barium	SW-6010	0.04	: 0.0838
Cadmium	SW-6010	0.005	: ND
Chromium	SW-6010	0.008	: ND
Lead	SW-6010	0.1	: ND
Mercury	SW-7470	0.0003	: ND
Selenium	SW-6010	0.1	: ND
Silver	SW-6010	0.05	: ND

ND = NOT DETECTED


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823005-2

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823005
DATE SAMPLED: 8-23-95
SAMPLE IDENTIFICATION: Water - Decon Water

DATE RECEIVED: 8-23-95
SAMPLED BY: Mick Cossairt

(TCLP) VOLATILE ORGANIC COMPOUNDS - SW-846-1311/8260

PARAMETER	DET. LIMIT (mg/L)	CONC. (mg/L)
Benzene	: 0.005	: ND
Carbon tetrachloride	: 0.005	: ND
Chlorobenzene	: 0.005	: ND
Chloroform	: 0.005	: ND
1,2-Dichloroethane	: 0.005	: ND
1,1-Dichloroethylene	: 0.005	: ND
Methyl ethyl ketone (2-Butanone)	: 0.02	: ND
Tetrachloroethylene	: 0.005	: ND
Trichloroethylene	: 0.005	: ND
Vinyl chloride	: 0.002	: ND

● = NOT DETECTED


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823005-3

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823005

DATE SAMPLED: 8-23-95

SAMPLE IDENTIFICATION: Water - Decon Water


DATE RECEIVED: 8-23-95

SAMPLED BY: Mick Cossairt

(TCLP) SEMI-VOLATILE ORGANIC COMPOUNDS - SW-846-1311/8270

PARAMETER	DET. LIMIT (mg/L)	CONC. (mg/L)
o-Cresol (2-Methylphenol)	: 0.02	: ND
m-Cresol (3-Methylphenol)	: 0.02	: ND
p-Cresol (4-Methylphenol)	: 0.02	: ND
Cresol (Total)	: 0.02	: ND
1,4-Dichlorobenzene	: 0.02	: ND
2,4-Dinitrotoluene	: 0.02	: ND
Hexachlorobenzene	: 0.02	: ND
Hexachloro-1,3-butadiene	: 0.02	: ND
Hexachloroethane	: 0.02	: ND
Nitrobenzene	: 0.02	: ND
Pentachlorophenol	: 0.10	: ND
Pyridine	: 4.00	: ND
2,4,5-Trichlorophenol	: 0.02	: ND
2,4,6-Trichlorophenol	: 0.02	: ND

ND = NOT DETECTED


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823005-4

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823005

DATE RECEIVED: 8-23-95

DATE SAMPLED: 8-23-95


SAMPLED BY: Mick Cossairt

SAMPLE IDENTIFICATION: Water - Decon Water

PCBS - EPA 608

PARAMETER	DET. LIMIT (ug/L)	CONC. (ug/L)
PCB-1016	: 2.0	: ND
PCB-1221	: 2.0	: ND
PCB-1232	: 2.0	: ND
PCB-1242	: 2.0	: ND
PCB-1248	: 2.0	: ND
PCB-1254	: 2.0	: ND
PCB-1260	: 2.0	: ND

ND = NOT DETECTED


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823004-1

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823004

DATE RECEIVED: 8-23-95

DATE SAMPLED: 8-23-95

SAMPLED BY: Mick Cossairt

SAMPLE IDENTIFICATION: Water - Development Water

PARAMETER	METHOD	DET. LIMIT (mg/L)	CONC. (mg/L)
TCLP - Metals	SW-1311		
Arsenic	SW-6010	0.1	: ND
Barium	SW-6010	0.04	: 0.340
Cadmium	SW-6010	0.005	: ND
Chromium	SW-6010	0.008	: ND
Lead	SW-6010	0.1	: ND
Mercury	SW-7470	0.0003	: ND
Selenium	SW-6010	0.1	: ND
Silver	SW-6010	0.05	: ND

ND = NOT DETECTED


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823004-2

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823004

DATE RECEIVED: 8-23-95

DATE SAMPLED: 8-23-95


SAMPLED BY: Mick Cossairt

SAMPLE IDENTIFICATION: Water - Development Water

(TCLP) VOLATILE ORGANIC COMPOUNDS - SW-846-1311/8260

PARAMETER	DET. LIMIT (mg/L)	CONC. (mg/L)
Benzene	: 0.005	: ND
Carbon tetrachloride	: 0.005	: ND
Chlorobenzene	: 0.005	: ND
Chloroform	: 0.005	: ND
1,2-Dichloroethane	: 0.005	: ND
1,1-Dichloroethylene	: 0.005	: ND
Methyl ethyl ketone (2-Butanone)	: 0.02	: ND
Tetrachloroethylene	: 0.005	: ND
Trichloroethylene	: 0.005	: ND
Vinyl chloride	: 0.002	: ND

ND = NOT DETECTED


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823004-3

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823004

DATE RECEIVED: 8-23-95

DATE SAMPLED: 8-23-95


SAMPLED BY: Mick Cossairt

SAMPLE IDENTIFICATION: Water - Development Water

(TCLP) SEMI-VOLATILE ORGANIC COMPOUNDS - SW-846-1311/8270

PARAMETER	DET. LIMIT (mg/L)	CONC. (mg/L)
o-Cresol (2-Methylphenol)	: 0.02	: ND
m-Cresol (3-Methylphenol)	: 0.02	: ND
p-Cresol (4-Methylphenol)	: 0.02	: ND
Cresol (Total)	: 0.02	: ND
1,4-Dichlorobenzene	: 0.02	: ND
2,4-Dinitrotoluene	: 0.02	: ND
Hexachlorobenzene	: 0.02	: ND
Hexachloro-1,3-butadiene	: 0.02	: ND
Hexachloroethane	: 0.02	: ND
Nitrobenzene	: 0.02	: ND
Pentachlorophenol	: 0.10	: ND
Pyridine	: 4.00	: ND
2,4,5-Trichlorophenol	: 0.02	: ND
2,4,6-Trichlorophenol	: 0.02	: ND

ND = NOT DETECTED


Norman L. Cunningham

Quality Analytical Services

1633 S. Marsh • Box 266426 • Kansas City, MO 64126 • (816) 254-5257

SERVICE TO: Industrial Service Corporation
: 1633 South Marsh
: Kansas City, MO 64126
:

REPORT #: 50823004-4

DATE: 10-17-95

ATTN: Brent Nickel

QAS #: 50823004

DATE RECEIVED: 8-23-95

DATE SAMPLED: 8-23-95

SAMPLED BY: Mick Cossairt

SAMPLE IDENTIFICATION: Water - Development Water

PCBS - EPA 608

PARAMETER	DET. LIMIT (ug/L)	CONC. (ug/L)
PCB-1016	: 2.0	: ND
PCB-1221	: 2.0	: ND
PCB-1232	: 2.0	: ND
PCB-1242	: 2.0	: ND
PCB-1248	: 2.0	: ND
PCB-1254	: 2.0	: ND
PCB-1260	: 2.0	: ND

ND = NOT DETECTED


Norman L. Cunningham